



QUOTE

Date
October 24, 2016

To: John Ross - Village of Oak Park
 123 Madison
 Oak Park, Illinois
 jross@oak-park.us

Job Description	Location	Width	Height	Square Ft.
Soundproof Wall - Option 1	Human Resource Offices	70.5	8	564

Quantity	Item Description	Per Unit	Total
38	Sheets of 5/8" drywall	\$9.25	\$351.50
5.0	5 gal. pails of sound damping compound	\$275.00	\$1375.00
10	Tubes of acoustic sealant	\$5.25	\$52.50
8	Rolls of Roxul Safe n' Sound	\$50.00	\$400.00
	Miscellaneous Materials		\$282.00

Labor Description	Total
Remove ceiling grid and acoustic ceiling tiles 4' from wall to allow adequate working space. Soundproof all electrical outlets. Attach two layers of drywall with one layer of damping compound to wall surface. Seal all perimeter edges with acoustic sealant. Build out all electrical outlets and ductwork. Tape and sand drywall. Replace ceiling grid, trim and install acoustic ceiling tiles.	\$7240.00
Install Roxul Safe n' Sound above ceiling grid	\$450.00

Total for materials and labor:	\$9701.00
With insulation install:	\$10151.00

Priming and painting is not included. A quote may be provided at the owners request.

www.soundproofchicago.com

708.307.5857