

					
ELECTRIC COMPANY	2830 COMMERCE STREET, FRANKLIN PARK, ILLINOIS 60131-2927 OFFICE PHONE: (708) 453-2222 / FACSIMILE: (708) 453-2851.				
H&H JOB #:	N/A				
IDOT ITEM #:	N/A				
DBE %:	0.00%				
ADDENDUM:	N/A				
LOCATION:	VILLAGE OF OAK PARK - 111 SOUTH MAPLE AVENUE - STREET LIGHTING WORK.				
CONTRACT #:	N/A				
COUNTY:	COOK				
SECTION #:	N/A				
ROUTE:	N/A				
DATE:	Friday, May 17, 2019				
BID AS:	GENERAL ELECTRICAL CONTRACTOR				
BID DUE DATE:	Friday, May 17, 2019				
BID DUE TIME:	5:00 PM				
BID LOCATION:	EMAIL TO MICHAEL KOPERNIAK AT THE ENGINEERING DIVISION FOR THE VILLAGE OF OAK PARK - mkoperniak@oak-park.us				
DUE TO OWNER (DATE):	Friday, May 17, 2019				
DUE TO OWNER (TIME):	5:00 PM				
COMPLETION:	WITHIN 2 WEEKS AFTER THE LAST OF THE FURNISHED MATERIAL HAS BEEN DELIVERED TO THE CONTRACTOR.				
ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE	TOTAL PRICE

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE	TOTAL PRICE
1	THIS WORK SHALL CONSIST OF REMOVING AN EXISTING THIRTEEN FOOT HIGH DIRECT BURIAL CONCRETE LIGHT POLE AND DELIVERING IT TO THE VILLAGE OF OAK PARK, FURNISHING AND INSTALLING AN 11"X18"X12" QUAZITE BOX AT THE SAME LOCATION, FURNISHING AND INSTALLING A NEW 22'-6" ABOVE GRADE DIRECT BURIAL CONCRETE LIGHT POLE WITH 6' MAST ARM AND COBRA HEAD FIXTURE APPROXIMATELY FOURTEEN FEET AWAY, FURNISHING AND INSTALLING NEW WIRING IN UNIT DUCT BETWEEN THE NEW LIGHT POLE AND THE QUAZITE BOX, SPLICING THE NEW WIRING TO THE EXISTING WIRING INSIDE THE QUAZITE BOX USING WATERPROOF SPLICES, RESTORING THE SOD PARKWAY, AND ALL OTHER APPURTENANT WORK NECESSARY TO MAKE THE NEW LIGHT POLE ASSEMBLY FULLY OPERATIONAL.	LUMP SUM	1.000	14,177.30	14,177.30
TOTALS					14,177.30
NOTES:					
1	THIS PROPOSAL IS BASED ON NORMAL WORKING HOURS.				
NOT INCLUDED IN THIS PROPOSAL:					
1	SPECIAL INSURANCE, FEES, OR PERMITS OF ANY TYPE.				
2	BONDS, ALTHOUGH WE ARE BONDABLE.				
3	NO WORK WILL BE DONE OTHER THAN THE ITEMS ON OUR BID WITHOUT WRITTEN APPROVAL.				
4	PROJECT LAYOUT INCLUDING GRADES AND ELEVATIONS.				
5	ANY AND ALL COSTS CONTRIBUTABLE TO TESTING, DOCUMENTATION, REMOVAL AND/OR DISPOSAL OF ANY SPOILS.				
6	ANY MAJOR SUBSURFACE OBSTACLES ENCOUNTERED WHICH CAUSES A DECREASE IN OUR PRODUCTION SHALL BE COMPENSATED AT TIME & MATERIAL RATES.				
7	HARD SURFACE REMOVAL & REPLACEMENT.				
8	ROCK EXCAVATION.				

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE	TOTAL PRICE
9	PROPOSAL VALID FOR <u>60</u> DAYS.				